

YCW VENEER SPECS		
Base Depth	2-3/8" or 3"	
Sightline	2" or 2-1/2"	
Config	Outside Glazed / Front Set	
Tested Glass	1" IGU with Low-E (C.O.G. U-Factor: 0.29)	
Test	Results	Standards
Air Infiltration	0.06 CFM/FT ² (1.10 m ³ /h·m ²) @ 6.24 PSF (299 Pa)	ASTM E 283
Water Infiltration	Static: 15 PSF (718 Pa) Dynamic: 15 PSF (718 Pa)	ASTM E 331 AAMA 501

Finish Options		
Туре	Standard	
Factory Anodized	AAMA 612	
Organic Paints	AAMA 2604 AAMA 2605	



YCW Veneer on wood substrate application - JST Production and Engineering Center

Veneer Attachment & Assembly

Shims are placed on the substrate to make the surface flush and fasteners are used securing the mullions in place, creating some spacing. Sealant is then applied over the shims for added stability and protection. After, the rest of the system is assembled, installing the glass and pressure plates. Lastly, the face covers snapped in.



Additional information including CAD details, CSI specs, test reports and installation instructions are found on the Product Guide by clicking this link or visiting www.ykkap.com/commercial/productguide

©2024 YKK AP America Inc. 04-5028-05